

BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of Work: Patching pot holes in main and cross roads of Balaji layout, Bhadrappa layout, Maruthinagara, BB Nagara, Shanthinikethana and Surroundings areas in ward no. 8

Sl. No.	Approved Qty.	Description	Unit	Issued to	
				Sanjayreddy H.J	
				In Figures	In Words
1	97.32	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	Cum	86.92	Rupees Eighty Six and Ninety Two Paise Only
2	64.81	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification NO. 406, Page No. 157 / Item No. 20.18 / PWD SR 2016-17	Cum	1768.08	Rupees One Thousand Seven Hundred Sixty Eight and Eight Paise Only
3	877.00	KSRRB 3000: Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications, MORTH specification No. 3004.2, No. 250 / Item No. 35.5 PWD SR 2016-17	Sqm	302.10	Rupees Three Hundred Two and Ten Paise Only
4	97.32	A) KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter 1 (Page No. 132 / Item No. 17.1)	Sqm	106.00	Rupees One Hundred Six Only

Signature of the Contractor

Sanjayreddy H.J
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

*Done
14/11*